

**EC COMPLIANCE REPORT
&
ENVIRONMENTAL STATUS REPORT
(December 2018 – May 2019)**

Of

Infosys IT/ITES Project

(EC Letter No. SEAC No. SEAC-III-2015/CR 92/TC-3 dtd. 28th January 2016)

Located At

**Survey No.55, 56, 57, 58, 59, 60, 62(p), 63, 64
(p), 65(p), 74 (p), 84(p), 85, 86, 87(p), 88, 89, 90,
91 (p), 92 (p), 93(p), 94(p), 95(p), 103(p),
At Village-Dahegaon, Tehsil & District - Nagpur**

Project Proponent

Infosys[®]

M/S. INFOSYS LIMITED

Environmental Consultant



***QCI-NABET Accredited EIA Consultant
MoEF&CC (GOI) Recognized and NABL Approved Laboratory
ISO 9001:2008, ISO 14001:2004, OHSAS 18001:2007***

60, Bajiprabhu Nagar, Nagpur - 440 033, MS

Lab. & Consultancy: FP-34, 35, Food Park,

MIDC, Butibori, Nagpur – 441122

Ph.: (0712) 2242077, 9373287475

Email: ngp@anacon.in

Website: www.anaconlaboratories.com

1st June 2019

INTRODUCTION

Infosys Limited (formerly Infosys Technologies Limited) is an Indian multinational corporation that provides business consulting, information technology and outsourcing services. It has its headquarters in Bengaluru, Karnataka, India.

It provides software development, maintenance and independent validation services to companies in finance, insurance, manufacturing and other domains

Infosys Limited has proposed their software development project in Nagpur, Maharashtra. This project has obtained environmental clearance from SEIAA, Maharashtra vide EC Letter No. SEAC-III-2015/CR 92/TC-3 dtd. 28th January 2016.

EC Conditions compliance status and Environmental monitoring reports for the period of **December 2018 – May 2019** is given below:

COMPLIANCE STATUS

Sr. No.	EC Conditions	Action Taken
General Conditions for Pre-Construction Phase		
I.	This environmental clearance is issued subject to land use verification. Local authority/planning authority should ensure this with respect to Rules, Regulations, Notifications, Government Resolution, Circulars, etc. issued if any. Judgments/orders issued by Hon'ble High Court, Hon'ble NGT, Hon'ble Supreme Court regarding DCR provisions, environmental issues applicable in this matter should be verified. PP should submit exactly the same plans appraised by concern SEAC and SEIAA. If any discrepancy found in the plans submitted or details provided in the above para may be reported to environmental consideration and it does not mean that State Level Impact Assessment Authority (SEIAA) approved the proposed land use.	Noted and Complied.
II.	E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2011.	E-waste will be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2011.
III.	Occupation certificate shall be issued to the project by Local Planning Authority only after ensuring availability of drinking water and connectivity of the sewer line to the project site.	PP complied with the same.
IV.	This environmental clearance is issued	Not Applicable as the land is not under

Sr. No.	EC Conditions	Action Taken
	subject to obtaining NOC form Forestry and Wild life angle including clearance from the standing committee of the National Board for Wildlife as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.	forest department land and has been given by MADC post all clearances.
V.	PP has to abide by the conditions stipulated by SEAC & SEIAA.	Noted & Agreed.
VI.	The height, construction build up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body and it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.	Noted & Complied.
VII.	“Consent for Establishment” shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.	“Consent for Establishment” is obtained from Maharashtra Pollution Control Board vide Consent Order No. Format 1.0/BO/CAC-Cell/NG-16706-15/CE/CAC-7893 dated 16/06/2016. Copy Attached in Annexure – I
VIII.	All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.	Noted & we will comply with the same.
General Conditions for Construction Phase-		
I.	Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche and First Aid Room etc.	There is no construction activity happening at site. We will ensure compliance to the same after start of the activity.
II.	Adequate drinking water and sanitary facilities should be provided for construction workers at the site.	We will ensure the same.

Sr. No.	EC Conditions	Action Taken
	Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.	
III.	The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.	Dry waste is currently being disposed-off to MADCL.
IV.	Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.	PP is compliant to the same
V.	Arrangement shall be made that waste water and storm water do not mixed.	Separate drain facility will be provided for waste water and storm water as a part of construction.
VI.	All the topsoil excavated during construction activities should be stored for use in horticulture/landscape development within the project site.	The topsoil has been stored & reused for the development of the green belt (Landscaping) within our campus. Cutting & filling of earth at site has been optimized.
VII.	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.	The topsoil has been stored & reused for the development of the green belt (Landscaping) within our campus. Cutting & filling of earth at site has been optimized.
VIII.	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/Agriculture Dept.	Total of 62,680 m ² area is provided for the development of Green belt in the premises. We have planted 182 Nos. of trees in the campus around the developed area as a green belt. We are in process of more tree plantation. Photos attached as Annexure – IV.
IX.	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals of other toxic contaminants.	Zero effluent discharge system is maintained at site. There is no underground leaching of wastewater. Monitoring report ground water quality is given below in status report as Annexure – VII.
X.	Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate	Noted and complied

Sr. No.	EC Conditions	Action Taken
	water courses and the dumpsites for such material must be secured so that they should not leach into the ground water.	
XI.	Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.	The Project being an IT park in nature is generating an insignificant quantity of hazardous waste. This will be disposed of as per applicable rules. Waste generated from the project site will be collected by Authorized vendor.
XII.	The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.	Diesel power generating sets proposed as source of backup power are of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of DG set stack is as per norms. We shall use low Sulphur diesel.
XIII.	The diesels required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.	Noted and Complied.
XIV.	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.	Noted and Complied. Sample PUC attached as Annexure – V.
XV.	Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.	Noted and Complied. Noise level monitoring is also carried out. (Please refer Environmental Parameters analysis report is enclosed in status report section) Noise Monitoring is attached in Annexure – VII.
XVI.	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27 th August 2003. (The above condition is applicable only if the project site is	We have used fly ash for construction of the existing buildings as per requirement. Currently there is no construction activity happening at the project site. We will ensure the compliance as applicable.

Sr. No.	EC Conditions	Action Taken
	located within the 100km of Thermal Power Stations).	
XVII.	Ready mixed concrete must be used in building construction.	We have used ready mix concrete during construction phase of existing structures. Currently there is no construction activity happening at the project site. We will ensure the compliance as applicable.
XVIII.	The approval of competent authority shall be obtained for structural safety of the buildings due to any possible earthquake, adequacy of firefighting equipment's etc. as per National Building Code including measures from lighting.	Noted & complied. Structural Safety Certificate obtained
XIX.	Storm water control and its re-use as per CGWB and BIS standards for various applications.	Storm water drainage system is designed as per CGWB and BIS Standards.
XX.	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.	We have used ready mix concrete during construction phase of existing structures. Currently there is no construction activity happening at the project site. We will ensure the compliance as applicable.
XXI.	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.	Complied. Monitoring Report is attached in Annexure-VII.
XXII.	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary	Sewage treatment plant (STP) (capacity 7 KLD) with SBR technology is in operation. All treated water is used for irrigation purpose. We are ensuring no odour from the STP. Installation of STP is certified by an independent expert and report is available with project proponent. STP Commissioning Report is attached in Annexure-VI.

Sr. No.	EC Conditions	Action Taken
	measures should be made to mitigate the odour problem from STP.	
XXIII.	Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to construction / operation of the project.	We do not draw Ground water. All water demand is met through MIHAN water supply & Tankers
XXIV.	Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.	Noted and complied by installing dual plumbing system.
XXV.	Fixtures for showers, toilet flushing and drinking should be low flow either by use of aerators or pressure reducing devices or sensor based control.	Noted & Complied. National Building Code measures implemented.
XXVI.	Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.	Noted & Complied. National Building Code measures implemented.
XXVII.	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.	Noted & Complied. National Building Code measures implemented.
XXVIII.	Energy conservation measures like installation of CFLs / TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non-conventional energy source as source of energy.	Noted & Complied. National Building Code measures implemented.

Sr. No.	EC Conditions	Action Taken
XXIX.	Diesel power generating sets proposed as source of backup power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.	Diesel power generating sets proposed as source of backup power are of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of DG set stack is as per norms. We are using low Sulphur diesel.
XXX.	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.	Noted & Complied. Noise monitoring reports area Attached in Annexure- VII .
XXXI.	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.	Noted & will ensure compliance.
XXXII.	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspiration for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.	Noted & Complied. National Building Code measures implemented.
XXXIII.	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.	Noted & Complied. National Building Code measures implemented.
XXXIV.	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.	Noted & Complied.
XXXV.	Under the provision of Environment	Noted.

Sr. No.	EC Conditions	Action Taken
	(Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.	
XXXVI.	Six monthly monitoring reports should be submitted to the Regional office, MoEF, Bhopal with copy to this department and MPCB.	Noted.
General Conditions for post-construction/operation phase-		
I.	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line. No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.	<p>We have already installed STP of capacity 7 KLD. No treated water is discharged outside the campus and the same is used for landscaping activity.</p> <p>Wet and dry waste is currently disposed-off to MADCL.</p> <p>We have planted 182 Nos. of trees in the campus around the developed area as a green belt. We are in process of more tree plantation.</p>
II.	Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.	Organic wet waste is segregated at the site. Wet garbage is currently disposed-off to MADCL.
III.	Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.	Noted & complied.
IV.	A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.	Noted & complied during half yearly compliance report submission.
V.	In case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.	Noted.

Sr. No.	EC Conditions	Action Taken
VI.	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.	Environmental Management Cell has been established.
VII.	Separate funds shall be allocated for implementation of environmental protection measure/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.	Noted and complied.
VIII.	The project management shall advertise at least in two local newspaper widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at http://ec.maharashtra.gov.in .	Attached is the copy of advertisement in the local newspapers. Attached as Annexure – III .
IX.	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1 st June & 1 st December of each calendar year.	Noted & being complied.
X.	A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestion / representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.	The clearance letter is put on the Company website. https://author1.infosys.com/sustainability/approvals/Documents/environmental-clearance-nagpur.pdf
XI.	The proponent shall upload the status of compliance of the stipulated EC	The Half yearly compliance report along with monitoring reports of criteria

Sr. No.	EC Conditions	Action Taken
	<p>conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.</p>	<p>pollutant levels are periodically uploaded on the company website. The same is also sent to Regional office of MoEFCC, respective zonal office of CPCB and the SPCB.</p>
XII.	<p>The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.</p>	<p>Noted and being complied every six months.</p>
XIII.	<p>The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.</p>	<p>We have received the 1st Consent to Operate (part) vide letter No. Format1.0/BO/CAC-cell/ UAN No. 0000022562/CO(part)/CAC-1811000120 on 2nd November 2018. Attached as Annexure – II.</p> <p>We will be submitting the environmental statement for FY ending 31st March 2019 in Form V by 31st September 2019 as per requirement.</p>

ENVIRONMENTAL STATUS REPORT

Air Quality Monitoring

Regular monitoring of environmental parameters is of immense importance to assess the status of environment. With the knowledge of baseline conditions, the monitoring program will serve as an indicator for any deterioration in environmental conditions due to construction projects. Suitable mitigation steps will be taken in time to safeguard the environment, based on monitoring reports. Monitoring is important in the control of pollution since the efficiency of control measures can only be determined by monitoring.

In order to find out the impact of various activities on sensitive receptors, it is necessary to monitor Environmental Quality to know the level of concentrations of pollutants within and around the Building premises.

Ambient Air Quality Monitoring

Ambient Air Quality was monitored at 3 locations within building premises. The sampling stations are selected at the above mentioned locations, in downwind and upwind directions of the Industry. ALPL is carrying out regular monitoring for, SPM, RPM, SO₂, NO_x and heavy metals at above Ambient Air Quality Monitoring (AAQM) locations.

Frequency of Sampling

Ambient air quality monitoring was carried out on 24 hourly on quarterly basis (once in a quarter) for the monitoring period.

Duration of Sampling

The duration of sampling for PM₁₀, PM_{2.5}, SO₂, NO_x and heavy metals is twenty-four hourly. Data is compared with the standards mentioned in the Gazette Notification of the Central Pollution Control Board (CPCB) Notification 16th Nov. 2009.

Methods and Instruments used for Sampling

The air samples were analyzed as per methods specified by Central Pollution Control Board (CPCB).

The levels of Suspended Particulate Matter, Respirable Particulate Matter, Sulphur Dioxide (SO₂), Oxides of Nitrogen (NO_x) & heavy metals were monitored for identifying the impact on surrounding area. PM₁₀ and PM_{2.5} were collected with the help of Respirable particulate sampler and Fine particulate sampler operating 24 hours and is computed by gravimetric method. Due to the high flow rate of air, the vacuum is formed into the hopper region of sampler which is tapped by providing a nozzle in the hopper which sucks the ambient air for sampling SO₂ and NO_x. The gases were measured by wet chemical method and were analyzed by colorimetric. The measurement techniques used for various pollutants and other details are given in below Table.

Measurement Techniques for Various Pollutants

Sr. No.	Parameter	Method	Technical Protocol	Minimum Detection limit ($\mu\text{g}/\text{m}^3$)
1.	Suspended Particulate Matter, SPM	Respirable Dust Sampler (Gravimetric Method)	IS-5182 (Part – IV)	5
2.	Respirable Particulate Matter, PM_{10}	Respirable Dust Sampler (Gravimetric Method)	IS-5182 (Part – IV)	5
3.	Fine Particulate Matter, $\text{PM}_{2.5}$	Fine Particulate Sampler (Gravimetric Method)	IS-5182 (Part-IV)	-
4.	Sulphur Dioxide	Improved West and Geake Method	IS-5182 (Part – II)	4
5.	Oxide of Nitrogen	Jacob & Hochheiser Modified Method	IS-5182 (Part – VI)	4
6.	Heavy Metals	Acid digestion	CPCB Guideline (Vol. 1)	0.0001

Annexure – I: Consent to Establish

MAHARASHTRA POLLUTION CONTROL BOARD

Tel: 24010706/ 24010437
 Fax: 24023516
 Website: <http://mpcb.gov.in>
 E-mail: cac-cell@mpcb.gov.in



Kalpataru Point, 2nd - 4th Floor
 Opp. Cine Planet Cinema,
 Near Sion Circle, Sion (E)
 Mumbai-400 022.

Consent order No: - Format 1.0/BO/CAC-cell/NG-16706-15/CE/CAC- 7893
 Date- 16/06/2016

To,
 M/s. Infosys Ltd. at S.No. 55 to 60, 62 (p), 63, 64(p), 65(p), 74(p), 75(p), 84(p), 85, 86, 87(p), 88 to 90, 91(p), 92(p), 93(p), 94(p), 95(p), 103(p), at village Dahegaon, Tehsil & Dist. Nagpur

Subject: Consent to Establish for construction of proposed IT/ITES project under RED category.
 Ref :

1. Your Application approved in 13th CAC meeting of 2015-2016 held on 25.01.2016

Your application CE1511000060
 Dated: 29.10.2015
 For: Consent to Establish for construction of proposed IT/ITES project under Section 25 of the Water (Prevention & Control of Pollution) Act, 1974 & under Section 21 of the Air (Prevention & Control of Pollution) Act, 1981 and Authorization under Rule 5 of the Hazardous Wastes (M, H & T M) Rules 2008 is considered and the consent is hereby granted subject to the following terms and conditions and as detailed in the schedule I, II, III & IV annexed to this order:

- The Consent to Establish (For Phase-I) is granted for a period up to: commissioning of the project or upto 5 years whichever is earlier.
- The proposed capital investment of the project is Rs. 400.3 crs (As per documents submitted by project proponent).
- The Consent to Establish is valid for construction of proposed IT/ITES project of M/s. Infosys Ltd. at S.No. 55 to 60, 62 (p), 63, 64(p), 65(p), 74(p), 75(p), 84(p), 85, 86, 87(p), 88 to 90, 91(p), 92(p), 93(p), 94(p), 95(p), 103(p), at village Dahegaon, Tehsil & Dist. Nagpur on Plot area of 5,75,364 sq.m. and total Construction BUA of 72,871 sq.m., including utilities and services as per construction commencement certificate issued by local body.
- Conditions under Water (P&CP), 1974 Act for discharge of effluent:

Sr. no.	Description	Permitted quantity of discharge (CMD)	Standards to be achieved	Disposal
1.	Trade effluent	Nil	NA	N.A.
2.	Domestic effluent	278	As per Schedule -I	The treated effluent shall be 100% recycled/ utilized for secondary purposes such as toilet flushing, air conditioning, firefighting and gardening etc.
- Conditions under Air (P&CP) Act, 1981 for air emissions:

Sr. No.	Description of stack/ source	Number Of Stack	Standards to be achieved
1	DG set (1x 1500 KVA)	1	As Per Schedule -II
2	DG set (1x 2000 KVA)	1	As Per Schedule -II

6. Conditions under Municipal Solid Waste (Management and Handling) Rule, 2000 :

Sr. No.	Type Of Waste	Quantity	Treatment	Disposal
1	Wet Garbage	1260 kg/day	Organic Waste Convertor (OWC)	use as manure
2	Dry Garbage	693 kg/day	-	Hand over to local body or sale for recycle
3	STP sludge	139 kg/day	-	use as manure

7. Conditions under E-Waste (Management and Handling) Rule, 2011 :


Sr. No.	Type Of Waste	Quantity	Treatment	Disposal
1	E-waste	1 T/Month	Nil	Through authorized recyclers

8. Conditions under Hazardous Waste (MH & TM) Rules, 2008 for treatment and disposal of hazardous waste

Sr. No.	Type Of Waste	Quantity	UOM	Treatment	Disposal
1	--	--	--	--	--

9. The Board reserves the right to review, amend, suspend, revoke etc. this consent and the same shall be binding on the industry.
10. This consent should not be construed as exemption from obtaining necessary NOC/permission from any other Government authorities.
11. Project Proponent shall submit the affidavit within 15 days in the prescribed format regarding the compliance of conditions of EIA Notification 2006/EC and Consent to Establish.
12. The applicant should not take any effective steps for implementation of the project before obtaining Environmental Clearance as per EIA Notification 2006 and amendments thereto. As per Para 2 of EIA notification dated-14/09/2006, the effective steps include starting of any construction work or preparation of land by the project management. However as clarified by the MoEF vide office memorandum no. J-1103/41/2006-IA.II(I); Dated-19/8/2010, fencing of the site to protect it from getting encroached & construction of temporary shed(s) for the guard(s) & acquisition of land shall not be treated as an effective steps.

For and on behalf of the
Maharashtra Pollution Control Board


(Dr. P. Anbalagan, IAS)
Member Secretary

Received Consent fee of -

Sr. No.	Amount(Rs.)	DD. No	Date	Drawn On
1	8,00,700/-	633780	29.09.2015	ICICI Bank

Copy to:

1. Regional Officer, Nagpur and Sub-Regional Officer MPCB, Nagpur-II
-- They are directed to ensure the compliance of the consent conditions.
2. Chief Accounts Officer, MPCB, Mumbai.
3. CC/CAC desk- for record & website updation purposes.

Schedule-I

Terms & conditions for compliance of Water Pollution Control:

- 1) A) As per your application, you have proposed to install Sewage Treatment Plants (STPs) with the design capacity of 280 CMD based on MBR Technology.
- B) The Applicant shall operate the effluent treatment plant (STP) to treat the sewage so as to achieve the following standards prescribed by the Board or under EP Act, 1986 and Rules made there under from time to time, whichever is stringent.


Sr No.	Parameters	Standards prescribed by Board
		Limiting Concentration in mg/l, except for pH
01	BOD (3 days 27oC)	10
02	Suspended Solids	10
03	COD	50
04	Residual Chlorine	1ppm

C) The treated effluent shall be 100% utilized/ recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting and gardening etc.. In no case, effluent shall find its way to any water body directly/indirectly at any time. Project proponent shall provide flow meter to ensure recycling of treated sewage and shall maintain the record with data logging system. Project Proponent shall achieve the treated domestic effluent standard for the parameter BOD- 10 mg/lit and shall install online monitoring system

- 2) The Board reserves its rights to review plans, specifications or other data relating to plant setup for the treatment of waterworks for the purification thereof & the system for the disposal of sewage or trade effluent or in connection with the grant of any consent conditions. The Applicant shall obtain prior consent of the Board to take steps to establish the unit or establish any treatment and disposal system or and extension or addition thereto.
- 3) The industry shall ensure replacement of pollution control system or its parts after expiry of its expected life as defined by manufacturer so as to ensure the compliance of standards and safety of the operation thereof.
- 4) In case, the water consumption of the project is not covered under the water consumption of local body, in that situation, the project proponent shall submit the CESS Returns in the prescribed format given under the provision of Water (Prevention & Control of Pollution) Cess Act, 1977 and Rules made there under for various category of water consumption.

In case the water consumption is duly assessed under the quantity of water consumption of local body, the project proponent shall submit certificate to that effect from the concern local body with the request not to assess CESS on their water consumption, being already assessed on the water consumption of local body.

Sr. no.	Purpose for water consumed	Water consumption quantity (CMD)
1.	Industrial Cooling, spraying in mine pits or boiler feed	Nil
2.	Domestic purpose	Fresh water: 207
3.	Processing whereby water gets polluted & pollutants are easily biodegradable	Nil
4.	Processing whereby water gets polluted & pollutants are not easily biodegradable and are toxic	Nil



Schedule-II

Terms & conditions for compliance of Air Pollution Control:

1. As per your application, you have proposed to install the Air pollution control (APC) system and also proposed to erect following stack (s) and to observe the following fuel pattern-

Sr. No.	Stack Attached To	APC System	Height in Mtrs.	Type Of Fuel	Quantity and UOM	S%
1	DG set (1x 1500 KVA)	Acoustic enclosure	7.7*	HSD	@ 0.21 liters/hr/KVA at full load.	1
2	DG set (1x 2000 KVA)	Acoustic enclosure	8.9*			

* Above roof of the building in which it is installed.

2. The applicant shall operate and maintain above mentioned air pollution control system, so as to achieve the level of pollutants to the following standards.

Particulate matter	Not to exceed	150 mg/Nm ³ .
--------------------	---------------	--------------------------

3. The Applicant shall obtain necessary prior permission for providing additional control equipment with necessary specifications and operation thereof or alteration or replacement alteration well before its life come to an end or erection of new pollution control equipment.
4. The Board reserves its rights to vary all or any of the condition in the consent, if due to any technological improvement or otherwise such variation (including the change of any control equipment, other in whole or in part is necessary).
5. Conditions for utilities like Kitchen, Eating Places:-
- The kitchen shall be provided with exhaust system chimney with oil catcher connected to chimney through ducting.
 - The toilet shall be provided with exhaust system connected to chimney through ducting.
 - The air conditioner shall be vibration proof and the noise shall not exceed 68 dB(A).
 - The exhaust hot air from A.C. shall be attached to Chimney at least 5 mtrs. higher than the nearest tallest building through ducting and shall discharge into open air in such a way that no nuisance is caused to neighbors.




Schedule-III
Details of Bank Guarantees

Proposed BG:

Sr. No.	Consent (C to E/O/R)	Amt of BG Imposed	Submission Period**	Purpose of BG #	Compliance Period	Validity++
1	Consent to Establish	Rs. 10 lakh	15 days from date of issue of consent	Towards compliance of Environmental Clearance Consent to Establish condition.	Validity of this consent	Validity of this consent + 4 months

** The above Bank Guarantee(s) shall be submitted by the applicant in favour of Regional Officer at the respective Regional Office within 15 days of the date of issue of Consent.

++ The Bank Guarantee(s) shall be valid for a period upto: Validity of consent + 4 months



Maharashtra Pollution Control Board


Schedule-IV

Conditions during construction phase:

a	During construction phase, applicant shall provide temporary sewage disposal and MSW facility for staff and worker quarters.
b	During construction phase, the ambient air and noise quality should be closely monitored to achieve Ambient Air Quality Standards and Noise by the project proponent through MoEF approved laboratory.
c	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.

General Conditions:

- 1) The applicant shall provide facility for collection of samples of sewage effluents, air emissions and hazardous waste to the Board staff at the terminal or designated points and shall pay to the Board for the services rendered in this behalf.
- 2) The firm shall strictly comply with the Water (P&CP) Act, 1974, Air (P&CP) Act, 1981 and Environmental Protection Act 1986 and Municipal Solid Waste (Management & Handling) Rule 2000, Noise (Pollution and Control) Rules, 2000 and E-Waste (Management & Handling Rule 2011.
- 3) Drainage system shall be provided for collection of sewage effluents. Terminal manholes shall be provided at the end of the collection system with arrangement for measuring the flow. No sewage shall be admitted in the pipes/sewers downstream of the terminal manholes. No sewage shall find its way other than in designed and provided collection system.
- 4) Vehicles hired for bringing construction material to the site should be in good condition and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- 5) Conditions for D.G. Set
 - a) Noise from the D.G. Set should be controlled by providing an acoustic enclosure or by treating the room acoustically.
 - b) Applicant should provide acoustic enclosure for control of noise. The acoustic enclosure/ acoustic treatment of the room should be designed for minimum 25 dB (A) insertion loss or for meeting the ambient noise standards, whichever is on higher side. A suitable exhaust muffler with insertion loss of 25 dB (A) shall also be provided. The measurement of insertion loss will be done at different points at 0.5 meters from acoustic enclosure/room and then average.
 - c) Applicant should make efforts to bring down noise level due to DG set, outside their premises, within ambient noise requirements by proper siting and control measures.
 - d) Installation of DG Set must be strictly in compliance with recommendations of DG Set manufacturer.
 - e) A proper routine and preventive maintenance procedure for DG set should be set and followed in consultation with the DG manufacturer which would help to prevent noise levels of DG set from deteriorating with use.
 - f) D.G. Set shall be operated only in case of power failure.
 - g) The applicant should not cause any nuisance in the surrounding area due to operation of D.G. Set.
 - h) The applicant shall comply with the notification of MoEF dated 17.05.2002 regarding noise limit for generator sets run with diesel.
- 6) Solid Waste – The applicant shall provide onsite municipal solid waste processing system & shall comply with Municipal Solid Waste (Management & Handling) Rule 2000 & E-Waste (M & H) Rule 2011.
- 7) Affidavit undertaking in respect of no change in the status of consent conditions and compliance of the consent conditions the draft can be downloaded from the official web site of the MPCB.
- 8) Applicant shall submit official e-mail address and any change will be duly informed to the MPCB.
- 9) The treated sewage shall be disinfected using suitable disinfection method.
- 10) The firm shall submit to this office, the 30th day of September every year, the environment statement report for the financial year ending 31st march in the prescribed Form-V as per the provision of rule 14 of the Environmental (Protection) Second Amended rule 1992.
- 11) **The applicant shall obtain Consent to Operate from Maharashtra Pollution Control Board before commissioning of the project.**



Annexure – II: Consent to Operate

MAHARASHTRA POLLUTION CONTROL BOARD

Tel: 24010706/ 24010437
 Fax: 24023516
 Website: <http://mpcb.gov.in>
 E-mail: cac-cell@mpcb.gov.in



Kalpataru Point, 2nd - 4th Floor
 Opp. Cine Planet Cinema,
 Near Sion Circle, Sion (E)
 Mumbai-400 022.

Consent order No: - Format1.0/BO/CAC-cell/UAN No. 0000022562/CO(Part)/CAC- **Date- 02/11/2018**

1811000120

To,

M/s.Infosys Limited
 S.No.55 to 60,62(pt),63,64(pt),65(pt),74(pt),75 (pt),84(pt),
 85,86,87(pt),88 to 90,91(pt),92(pt),93(pt),94(pt),95(pt),103(pt)
 at village Dahegaon, Tahsil & Dist-Nagpur,Maharashtra.

Subject: 1st Consent to Operate (Part) for IT &ITES Project in RED Category.

Ref : 1. Consent to Establish granted by Board vide no.BO/CAC-Cell/NG-16706-15/CE/CAC-7893 Dated 16.6.2016.
 2. Environment Clearance accorded by Env. Dept.,GoM vide No. SEAC-III-2015 /CR.92/TC.3 dtd. 28.01.2016.

Minutes of Consent Appraisal Committee (CAC) meeting held on **8.8.2017**

Your application No.0000022562 Dated 7.03.2017.

For: 1st Consent to Operate (Part)

under Section 26 of the Water (Prevention & Control of Pollution) Act, 1974 & under Section 21 of the Air (Prevention & Control of Pollution) Act, 1981 and Authorization under Rule 6 of the Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 is considered and the consent is hereby granted subject to the following terms and conditions and as detailed in the schedule I, II, III & IV annexed to this order:

- The 1st Consent to Operate (Part) is valid for period upto **31.8.2019**.
- The **capital investment of the project (Part) is Rs. 21 Cr As per undertaking submitted by project proponent** and as per C to E dated 16.6.2016, Capital Investment of complete project is Rs. 400.3 Cr.
- The 1st Consent to Operate (Part) is valid for IT &ITES Project named as M/s.Infosys Limited., S.No.55 to 60, 62(pt), 63, 64(pt), 65(pt), 74(pt),75 (pt),84(pt),85,86,87(pt),88 to 90, 91(pt), 92(pt), 93(pt), 94(pt), 95(pt),103(pt) at village Dahegaon, Tahsil & Dist-Nagpur, Maharashtra **for total plot area of 5,75,364.371 Sq. Mtrs and construction BUA of 2449.785 Sq. Mtrs out of Total construction BUA of 72,871 Sq. Mtrs** as per EC dated 28.1.2016 including utilities and services.

4. Conditions under Water (P&CP), 1974 Act for discharge of effluent:

Sr. no.	Description	Permitted quantity of discharge (CMD)	Standards to be achieved	Disposal
1.	Trade effluent	NIL	NA	NA
2.	Domestic effluent	6	As per Schedule -I	The treated effluent shall be 60% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be connected to the sewerage system provided by local body

Infosys Ltd/CO (Part)/UAN 0000022562 Page 1 of 6

5. Conditions under Air (P& CP) Act, 1981 for air emissions:

Sr. No.	Description of stack/ source	Number Of Stack	Standards to be achieved
1	DG set (160 KVA)	1	As Per Schedule -II

6. Conditions under Municipal Solid Waste (Management and Handling) Rule, 2000 :

Sr. no.	Type Of Waste	Quantity	Treatment	Disposal
1	Biodegradable	75 Kg/day	OWC provided	Used as Manure
2	Non-Biodegradable	50 Kg/day	---	Segregate and Hand over to Local Body for recycling
3	STP Sludge	140 Kg/Day	--	Used as Manure

7. Conditions under Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 for treatment and disposal of hazardous waste

Sr. No.	Type Of Waste	Quantity	UOM	Treatment	Disposal
NIL					

8. The Board reserves the right to review, amend, suspend, revoke etc. this consent and the same shall be binding on the industry.
9. This consent should not be construed as exemption from obtaining necessary NOC/permission from any other Government authorities.
10. PP shall submit undertaking in Board prescribed format within 15 days regarding compliance of conditions of Environmental Clearance (EC) and Consent to Establish.
11. PP shall submit the undertaking within 15 days in the prescribed format regarding the part of the built-up area/ building for which application for 1st Consent to Operate (Part) is made and that the same is included in the Environmental Clearance accorded.
12. Project Proponent shall extend/ submit the BG of Rs. 25 lakhs towards O & M of pollution control system.
13. PP shall achieve the treated domestic effluent standard for the parameter BOD- 10 mg/lit.
14. The treated domestic effluent shall be 100% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be utilized on land for gardening.
15. PP shall comply conditions stipulated in Environmental clearance issued by Env. Dept ,GoM vide No. SEAC-III/CR.92/TC.3 dtd. 28.1.2016.

For and on behalf of the
Maharashtra Pollution Control Board

(E. Ravendiran, IAS)
Member Secretary

Received Consent fee of –

Sr. No.	DR No.	Bank Name	Amount	date
1	TXN1703001030	--	50,000/-	9.3.2017
2.	7616029	Deutsche Bank	50,000/-	23.10.2018

Copy to:

1. Regional Officer, MPCB, Nagpur and Sub-Regional Officer, MPCB, Nagpur-I
-- They are directed to ensure the compliance of the consent conditions.
2. Chief Accounts Officer, MPCB, Mumbai.
3. CC/CAC desk- for record & website updation purposes.

Schedule-I

Terms & conditions for compliance of Water Pollution Control:

- 1) A) As per your application, you have provided Sewage Treatment Plant (STP) of capacity 7 CMD of MBBR Technology.
- 2) B) The Applicant shall operate the effluent treatment plant (STP) to treat the sewage so as to achieve the following standards prescribed by the Board or under EP Act, 1986 and Rules made there under from time to time, whichever is stringent.

Sr No.	Parameters	Standards prescribed by Board
		Limiting Concentration in mg/l, except for pH
01	BOD (3 days 27°C)	10
02	Suspended Solids	10
03	COD	50
04	Residual Chlorine	1ppm

C) The treated domestic effluent shall be 60% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be utilized on land for gardening and connected to the sewerage system provided by local body. In no case, effluent shall find its way to any water body directly/indirectly at any time. Project proponent shall provide flow meter to ensure 60% recycling of treated sewage and shall maintain the record with data logging system. **PP shall achieve the treated domestic effluent standard for the parameter BOD- 10 mg/lit.**

- 3) The Board reserves its rights to review plans, specifications or other data relating to plant setup for the treatment of waterworks for the purification thereof & the system for the disposal of sewage or trade effluent or in connection with the grant of any consent conditions. The Applicant shall obtain prior consent of the Board to take steps to establish the unit or establish any treatment and disposal system or an extension or addition thereto.
- 4) The industry shall ensure replacement of pollution control system or its parts after expiry of its expected life as defined by manufacturer so as to ensure the compliance of standards and safety of the operation thereof.
- 5) **The Applicant shall comply with the provisions of the Water (Prevention & Control of Pollution) Act, 1974 and as amended, and other provisions as contained in the said act.**

Sr. no.	Purpose for water consumed	Water consumption quantity (CMD)
1.	Industrial Cooling, spraying in mine pits or boiler feed	0.00
2.	Domestic purpose	7
3.	Processing whereby water gets polluted & pollutants are easily biodegradable	0.00
4.	Processing whereby water gets polluted & pollutants are not easily biodegradable and are toxic	0.00



Schedule-II

Terms & conditions for compliance of Air Pollution Control:

1. As per your application, you have proposed to installed the Air pollution control (APC) system and also erected following stack (s) and to observe the following fuel pattern-

Sr. No.	Stack Attached To	APC System	Height in Mtrs.	Type of Fuel	Quantity & UoM
01.	DG set (160 KVA)	Acoustic Enclosure	16.5*	Diesel	8.64 Ltr/hr

* Above roof of the building in which it is installed.

2. The applicant shall operate and maintain above mentioned air pollution control system, so as to achieve the level of pollutants to the following standards.

Particulate matter	Not to exceed	150 mg/Nm ³
--------------------	---------------	------------------------

3. The Applicant shall obtain necessary prior permission for providing additional control equipment with necessary specifications and operation thereof or alteration or replacement alteration well before its life come to an end or erection of new pollution control equipment.
4. The Board reserves its rights to vary all or any of the condition in the consent, if due to any technological improvement or otherwise such variation (including the change of any control equipment, other in whole or in part is necessary).



Schedule-III
Details of Bank Guarantees

Sr. No.	Consent	Amt of BG Imposed	Submission Period**	Purpose of BG #	Compliance Period	Validity
1	1 st C to O(Part)	Extend/submit the BG of Rs.25 Lakh	15 Days	Towards O and M Pollution Control system	Continuous	31.12.2019

* The above Bank Guarantee(s) shall be submitted by the applicant in favour of Regional Officer at the respective Regional Office within 15 days of the date of issue of Consent.

++ The Bank Guarantee(s) shall be valid for a period upto: Validity of consent + 4 months.

Existing BG obtained for above purpose if any may be extended for period of validity as above.



Maharashtra Pollution Control Board

Schedule-IV**General Conditions:**

- 1) The applicant shall provide facility for collection of samples of sewage effluents, air emissions and hazardous waste to the Board staff at the terminal or designated points and shall pay to the Board for the services rendered in this behalf.
- 2) The firm shall strictly comply with the Water (P&CP) Act, 1974, Air (P&CP) Act, 1981 and Environmental Protection Act 1986 and Municipal Solid Waste (Management & Handling) Rule 2000, Noise (Pollution and Control) Rules, 2000 and E-Waste (Management & Handling) Rule 2011.
- 3) Drainage system shall be provided for collection of sewage effluents. Terminal manholes shall be provided at the end of the collection system with arrangement for measuring the flow. No sewage shall be admitted in the pipes/sewers downstream of the terminal manholes. No sewage shall find its way other than in designed and provided collection system.
- 4) Vehicles hired for bringing construction material to the site should be in good condition and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- 5) Conditions for D.G. Set
 - a) Noise from the D.G. Set should be controlled by providing an acoustic enclosure or by treating the room acoustically.
 - b) Applicant should provide acoustic enclosure for control of noise. The acoustic enclosure/ acoustic treatment of the room should be designed for minimum 25 dB (A) insertion loss or for meeting the ambient noise standards, whichever is on higher side. A suitable exhaust muffler with insertion loss of 25 dB (A) shall also be provided. The measurement of insertion loss will be done at different points at 0.5 meters from acoustic enclosure/room and then average.
 - c) Applicant should make efforts to bring down noise level due to DG set, outside their premises, within ambient noise requirements by proper siting and control measures.
 - d) Installation of DG Set must be strictly in compliance with recommendations of DG Set manufacturer.
 - e) A proper routine and preventive maintenance procedure for DG set should be set and followed in consultation with the DG manufacturer which would help to prevent noise levels of DG set from deteriorating with use.
 - f) D.G. Set shall be operated only in case of power failure.
 - g) The applicant should not cause any nuisance in the surrounding area due to operation of D.G. Set.
 - h) The applicant shall comply with the notification of MoEF dated 17.05.2002 regarding noise limit for generator sets run with diesel.
- 6) Solid Waste – The applicant shall provide onsite municipal solid waste processing system & shall comply with Municipal Solid Waste (Management & Handling) Rule 2000 & E-Waste (M & H) Rule 2011.
- 7) Affidavit undertaking in respect of no change in the status of consent conditions and compliance of the consent conditions the draft can be downloaded from the official web site of the MPCB.
- 8) Applicant shall submit official e-mail address and any change will be duly informed to the MPCB.
- 9) The treated sewage shall be disinfected using suitable disinfection method.
- 10) The firm shall submit to this office, the 30th day of September every year, the environment statement report for the financial year ending 31st march in the prescribed Form-V as per the provision of rule 14 of the Environmental (Protection) Second Amended rule 1992.
- 11) **The applicant shall make an application for renewal of the consent at least 60 days before date of the expiry of the consent.**

-----0000-----

Annexure – III: Paper Advertisement

Annexure – IV: Site Photographs



Annexure – V: PUC

MAHARASHTRA MOTOR VEHICLES DEPARTMENT
POLLUTION TEST CERTIFICATE FOR DIESEL & HEAVY VEHICLES

Motor Vehicle No.	MH. 49. AT. 0698
Date of Issue	27/12/2018
Date of Expiry	26/06/2019
Serial Number	I.P.S. 3/4W-A
	834379
	VALID ALL OVER INDIA
Emission Test Result	
Smoke Density in Hartridge Smoke Units	16%

Annexure – VI: STP Commissioning Report



Date: 08/03/2017

To,
Infosys Limited
Nagpur

Sub: Installation & Commissioning report of STP Nagpur.

Further to the above subject, this is to inform that Sewage Treatment Plant Capacity of 7 KLD is supplied and installed by Sobha Limited.

STP was installed and commissioned with fresh water on 06.03.17.

Thanking You,



K. K. K...
For Sobha Limited,

For Infosys Limited

Annexure - VII

Test Report

December 2018



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/518-1

Issue Date : 31/12/2018

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-340-1
Sample Description : Ambient Air
Sample Drawn On : 20/12/2018 To 21/12/2018
Sample Drawn By : Anacon Representative
Sample Received On : 24/12/2018
Sampling Location : Near Main Gate
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 24/12/2018 To 25/12/2018
Sampling Time : 24 Hrs.
Ambient Temperature : 23°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.4 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	54.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	18.3	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	9.4	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	21.8	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.371	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	6.3	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	8.7	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Chemist: *Smita*
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
Support Helplines : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacoin.in. You may also visit us at www.anacoinlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

K. Saigamkar
Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/518-2

Issue Date : 31/12/2018


Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-340-2
Sample Description : Ambient Air
Sample Drawn On : 20/12/2018 To 21/12/2018
Sample Drawn By : Anacon Representative
Sample Received On : 24/12/2018
Sampling Location : Near DG Set
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 24/12/2018 To 25/12/2018
Sampling Time : 24 Hrs.
Ambient Temperature : 23°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	58.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	27.9	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	8.1	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	28.4	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.416	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	7.3	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	12.4	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Chemist: *Sand*   Authorized Signatory

Address : Infosys Limited, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924. Email : nnp@anacon.in
Lab : FP 34-35, Food Park, Elite Staff Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475. Email : labngp@anacon.in
Support Helpline : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/518-3

Issue Date : 31/12/2018

Issued To : **Infosys Limited**
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-340-3
Sample Description : Ambient Air
Sample Drawn On : 20/12/2018 To 21/12/2018
Sample Drawn By : Anacon Representative
Sample Received On : 24/12/2018
Sampling Location : Near Canteen
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 24/12/2018 To 25/12/2018
Sampling Time : 24 Hrs.
Ambient Temperature : 23°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.4 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	52.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	17.3	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	5.8	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	16.9	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.284	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	5.6	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	7.9	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Chemist: *Smit*
Authorized Signatory
Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924. Email : ngp@anaconlabs.com
Lab : FF 34-35, Food Park, Elve Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helplines : Technical (9373267475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

NOISE MONITORING REPORT

Report No.:-	AN/NE/IL/2018-19/518	Report Date:-	31.12.2018
Issued to :-	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7, Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Noise Monitoring (December-2018)	Sample Ref.No.	1819/Mon-N-340
Sample Drawn By	Anacon Representative	Data Received :	21.12.2018

SL. NO.	LOCATION	Date of Sampling	RESULT (dBA)	
			Day Time	Night Time
1.	Near Main Gate	20.12.2018	61.7	56.3
2.	Near DG Set	20.12.2018	56.3	42.8
3.	Near Canteen	20.12.2018	51.9	41.6
CPCB Standards				
Industrial Area			75	70
Residential Area			55	45

Thanks for utilizing our services.

Chemist:- *S. Suf.*

J. Jayankar
Authorized Signatory

Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Bulburi, Nagpur - 441122. Mob. No. 9373267475, Email : labngp@anacon.in
Support Helpline : Technical (9373267475), Accounts Division (9326990081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



Annexure - VII

Test Report

January 2019



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/594-1

Issue Date : 31/01/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-385-1
Sample Description : Ambient Air
Sample Drawn On : 24/01/2019 To 25/01/2019
Sample Drawn By : Anacon Representative
Sample Received On : 25/01/2019
Sampling Location : **Near Main Gate**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 28/01/2019 To 29/01/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 24°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear


S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	58.3	µg / m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	23.9	µg / m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	11.4	µg / m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	27.8	µg / m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.371	mg / m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg / m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	7.3	µg / m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	9.8	µg / m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg / m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Bajirabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
Floor 21-25, Food Park, Elite Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
Support Helpline - Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
Email : support@anacoin.in. You may also visit us at www.anacoinlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory





TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/594-2

Issue Date : 31/01/2019

Issued To : **Infosys Limited**
Nagpur SEZ Co-Developer,
Plot No.7,Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-385-2
Sample Description : Ambient Air
Sample Drawn On : 24/01/2019 To 25/01/2019
Sample Drawn By : Anacon Representative
Sample Received On : 25/01/2019
Sampling Location : **Near DG Set**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 28/01/2019 To 29/01/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 24°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	52.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	21.9	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	8.1	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	24.6	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.352	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	6.8	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	9.4	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Bajirabhanagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
Lab : EB-31-25, Connaught Place Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
Support : Maharashtra Technical (9373287475), Accounts Division (9328960081, 9372960079), Administration (9372960079)
Email : support@anacoin.in / You may also visit us at www.anacoinlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/594-3

Issue Date : 31/01/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7,Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-385-3
Sample Description : Ambient Air
Sample Drawn On : 24/01/2019 To 25/01/2019
Sample Drawn By : Anacon Representative
Sample Received On : 25/01/2019
Sampling Location : **Near Canteen**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 28/01/2019 To 29/01/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 24°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.4 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	48.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	17.6	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	5.9	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	16.4	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.293	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	5.8	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	7.3	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Brijnagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Four Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Branches : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory





TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Test Report No. : ALPL/31012019/595

Page 1 of 2

Issued To : Infosys Limited Nagpur SEZ Co-Developer, Plot No.7, Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.	Sample Inward No. 1819/Mon-385-DW-1	Analysis Start 28.01.2019
	Inward Date 25.01.2019	Analysis End 31.01.2019
	P.O.NO. 2300129089	Report Issue Date 31.01.2019
	Date 04.06.2018	Sample Category Water
Sample Name Drinking Water	Sample Collected By Anacon Representative	Quantity Received 2 Lit. & 250ml
Sampling Location Canteen	Sampling Date 24.01.2019	Sampling Time 3.10 P.M.

TEST RESULTS

Sr. No.	Test Parameter	Measurement Unit	Test Method	As per IS 10500 : 2012 (Drinking Water - Specification)		Test Result
				Acceptable Limit	*Permissible Limit	
1.	pH value	-	IS 3025 (Part 11)	6.5 to 8.5	No relaxation	6.87at 25°C
2.	Electrical Conductivity	µs/cm	IS 3025 (Part 14)	--	--	437.2
3.	Turbidity	NTU	IS 3025 (Part 10)	1	5	0.2
4.	Colour	Hazen units	IS 3025 (Part 4)	5	15	1
5.	Odour	-	IS 3025 (Part 5)	Agreeable	Agreeable	Agreeable
6.	Iron (as Fe)	mg/l	IS 3025 (Part 2)	1.0	No relaxation	0.06
7.	Free residual chlorine	mg/l	IS 3025 (Part 26)	Min. 0.2	1	< 0.1
8.	Total dissolved solids	mg/l	IS 3025 (Part 16)	500	2000	162
9.	Fluoride (as F)	mg/l	IS 3025 (Part 60)	1.0	1.5	0.14
10.	Cyanide (as CN)	mg/l	IS 3025 (Part 27)	0.05	No relaxation	< 0.005
11.	Chloride (as Cl)	mg/l	IS 3025 (Part 32)	250	1000	31.64
12.	Total Alkalinity (as CaCO ₃)	mg/l	IS 3025 (Part 23)	200	600	27.92
13.	Total hardness (as CaCO ₃)	mg/l	IS 3025 (Part 21)	200	600	80.85
14.	Total Carbonate	mg/l	IS 3025 (Part 51)	--	--	Absent
15.	Bicarbonate	mg/l	IS 3025 (Part 51)	--	--	38.46
16.	Calcium (as Ca)	mg/l	IS 3025 (Part 40)	75	200	24.52
17.	Magnesium (as Mg)	mg/l	IS 3025 (Part 46)	30	100	4.76
18.	Sulphate (as SO ₄)	mg/l	IS 3025 (Part 24)	200	400	16.91
19.	Nitrate (as NO ₃)	mg/l	APHA Method	45	No relaxation	< 2
20.	Sodium (as Na)	mg/l	IS 3025 (Part 45)	--	--	3.97
21.	Potassium (as K)	mg/l	IS 3025 (Part 45)	--	--	1.03

NOTES: ● Please see watermark "Original Test Report" to confirm the authenticity of this report. ● Results shall be referred to tested sample(s) and applicable to tested parameter's only. ● Test report shall not be reproduced except in full without prior written approval of Anacon Labs. ● Liability of Anacon Labs is limited to invoiced amount only. ● Non-perishable and perishable sample(s) shall be disposed off after 30 days and 15 days respectively from the date of issue of Test Report, unless specified otherwise. ● #Permissible limit in absence of an alternate source for drinking water. ● MPN indicates most probable number. ● 'mg/l' is equivalent to 'ppm'. ● 'µg/l' is equivalent to 'ppb'. ● '<' Indicates detection limit of instrument/method and shall be considered as 'absent'. ● Result for test no. 7 is not relevant.

For ANACON LABORATORIES PVT. LTD.

Verified by

Authorized Signatory

Head Office: Infosys Estate, MIDC Butibori, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacn.in
 Lab : FP 3/05, Food Park, Infosys Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacn.in
 Support Offices - Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
 Email : support@anacn.in. You may also visit us at www.anacnlaboratories.com
 Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

(Mrs.) S.D. Garway
(Director - Labs)



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Test Report No. : ALPL/31012019/595

Page 2 of 2

Issued To : Infosys Limited Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.	Sample Inward No. 1819/Mon-385-DW-1	Analysis Start 28.01.2019
	Inward Date 25.01.2019	Analysis End 31.01.2019
	P.O.NO. 2300129089	Report Issue Date 31.01.2019
	Date 04.06.2018	Sample Category Water
Sample Name Drinking Water	Sample Collected By Anacon Representative	Quantity Received 2 Lit. & 250ml
Sampling Location Canteen	Sampling Date 24.01.2019	Sampling Time 3.10 P.M.

TEST RESULTS

Sr. No	Test Parameter	Measurement Unit	Test Method	As per IS 10500 : 2012 (Drinking Water - Specification)		Test Result
				Acceptable Limit	*Permissible Limit	
22.	Dissolved Oxygen	mg/l	IS : 3025 (Part 38)	--	--	6.1
23.	Copper (as Cu)	mg/l	IS 3025 (Part 2)	0.05	1.5	< 0.03
24.	Manganese (as Mn)	mg/l	IS 3025 (Part 2)	0.1	0.3	< 0.05
25.	Mercury (as Hg)	mg/l	IS : 3025 (Part 48)	0.001	No relaxation	ND
26.	Cadmium (as Cd)	mg/l	IS : 3025 (Part 41)	0.003	No relaxation	< 0.001
27.	Selenium (as Se)	mg/l	IS : 3025 (Part 56)	0.01	No relaxation	< 0.001
28.	Arsenic (as As)	mg/l	IS : 3025 (Part 37)	0.01	No relaxation	< 0.01
29.	Aluminium (as Al)	mg/l	IS : 15302	0.03	0.2	< 0.005
30.	Lead (as Pb)	mg/l	IS : 3025 (Part 47)	0.01	No relaxation	< 0.001
31.	Zinc (as Zn)	mg/l	IS 3025 (Part 2)	5	15	< 0.01
32.	Total Chromium (as Cr)	mg/l	IS 3025 (Part 2)	0.05	No relaxation	< 0.03
33.	Boron (as B)	mg/l	IS 3025 (Part 2)	0.5	2.4	< 0.1
34.	Phenolic compounds (as C ₆ H ₅ OH)	mg/l	IS 3025 (Part 43) :1001	0.001	0.002	< 0.001
35.	Anionic detergents (as MBAS)	mg/l	IS 13428:2005 (Annex K)	0.2	1.0	< 0.01
36.	Total coliform	Per 100 ml	IS 15185	Absent	Absent	Absent
37.	<i>Escherichia coli</i>	Per 100 ml	IS 15185	Absent	Absent	Absent

NOTES: ● Please see watermark "Original Test Report" to confirm the authenticity of this report. ● Results shall be referred to tested sample(s) and applicable to tested parameters only. ● Test report shall not be reproduced except in full without prior written approval of Anacon Labs. ● Liability of Anacon Labs is limited to invoiced amount only. ● Non-perishable and perishable sample(s) shall be disposed off after 30 days and 15 days respectively from the date of issue of Test Report, unless specified otherwise. ● *Permissible limit in absence of an alternate source for drinking water. ● MPN indicates most probable number. ● 'mg/l' is equivalent to 'ppm'. ● 'µg/l' is equivalent to 'ppb'. ● '<' indicates detection limit of instrument/method and shall be considered as 'absent'. ● Result for test no. 7 is not relevant.

REMARKS: Based upon request of the party, sample was tested for above mentioned parameters only. Sample complies with IS:10500:2012, for test conducted, indicating that it is fit for drinking purpose with respect to tested parameters.

For ANACON LABORATORIES PVT. LTD.

Verified by

Authorized Signatory

Head Office: Infosys Food Park, Five Star Estate, MIDC Butibori, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoinlab.com
 Lab : FP 3025 Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoinlab.com
 Support Head Office : Technical (9373287475), Accounts Division (9326960061, 9372960079), Administration (9372960078)
 Email : support@anacoinlab.com. You may also visit us at www.anacoinlaboratories.com
 Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

(Mrs) S.D. Garway
(Director - Labs)



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

NOISE MONITORING REPORT

Report No.:-	AN/NE/IL/2018-19/594	Report Date:-	31/01/2019
Issued to :-	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Noise Monitoring (January-2019)	Sample Ref.No.	1819/Mon-N-385
Sample Drawn By	Anacon Representative	Data Received :	25.01.2019

SL. NO.	LOCATION	Date of Sampling	RESULT (dBA)	
			Day Time	Night Time
1.	Near Main Gate	24.01.2019	64.7	56.1
2.	Near DG Set	24.01.2019	61.2	48.3
3.	Near Canteen	24.01.2019	54.9	42.6
CPCB Standards				
Industrial Area			75	70
Residential Area			55	45

Thanks for utilizing our services.

Chemist:- *Sony*

[Signature]
Authorized Signatory



Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helpline : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Annexure - VII

Test Report

February 2019



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/663-1

Issue Date : 26/02/2019

Issued To : **Infosys Limited**
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-422-1
Sample Description : Ambient Air
Sample Drawn On : 20/02/2019 To 21/02/2019
Sample Drawn By : Anacon Representative
Sample Received On : 22/02/2019
Sampling Location : **Near Main Gate**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 22/02/2019 To 23/02/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 26°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	57.1	µg / m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	22.7	µg / m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	9.2	µg / m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	26.4	µg / m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.391	mg / m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg / m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	6.8	µg / m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	9.2	µg / m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg / m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 80, Bellipokhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Parkstar Estate, MIDC Bullburi, Nagpur - 441122. Mob. No. 9373267475, Email : labngp@anacon.in
Chemistry : Technical (9373267475), Accounts Division (9326960061, 9372960079), Administration (9372960079)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/663-2

Issue Date : 26/02/2019

Issued To : **Infosys Limited**
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-422-2
Sample Description : Ambient Air
Sample Drawn On : 20/02/2019 To 21/02/2019
Sample Drawn By : Anacon Representative
Sample Received On : 22/02/2019
Sampling Location : Near DG Set
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 22/02/2019 To 23/02/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 26°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	53.9	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	17.2	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	7.3	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	21.8	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.341	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	6.2	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	8.4	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Baliprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, First Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Chemistry Division (9373287475), Accounts Division (9328980081, 9372960079), Administration (9372960079)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/663-3

Issue Date : 26/02/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-385-3
Sample Description : Ambient Air
Sample Drawn On : 20/02/2019 To 21/02/2019
Sample Drawn By : Anacon Representative
Sample Received On : 22/02/2019
Sampling Location : **Near Canteen**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 22/02/2019 To 23/02/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 26°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.4 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	47.2	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	16.1	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	6.2	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	17.6	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.309	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	5.3	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	7.1	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)


Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Bajirabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, One Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Chemist: *Smit* (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com

Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Gang
Authorized Signatory





TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Test Report No. : ALPL/26022019/664

Page 1 of 2

Issued To : Infosys Limited Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.	Sample Inward No. 1819/Mon-422-DW-1	Analysis Start 22.02.2019
	Inward Date 22.02.2019	Analysis End 26.02.2019
	P.O.NO. 2300129089	Report Issue Date 26.02.2019
	Date 04.06.2018	Sample Category Water
Sample Name Drinking Water	Sample Collected By Anacon Representative	Quantity Received 2 Lit. & 250ml
Sampling Location Canteen	Sampling Date 21.02.2019	Sampling Time 12.40 P.M.

TEST RESULTS

Sr. No.	Test Parameter	Measurement Unit	Test Method	As per IS 10500 : 2012 (Drinking Water - Specification)		Test Result
				Acceptable Limit	*Permissible Limit	
1.	pH value	-	IS 3025 (Part 11)	6.5 to 8.5	No relaxation	6.92 at 25°C
2.	Electrical Conductivity	µs/cm	IS 3025 (Part 14)	--	--	416.3
3.	Turbidity	NTU	IS 3025 (Part 10)	1	5	0.3
4.	Colour	Hazen units	IS 3025 (Part 4)	5	15	1
5.	Odour	-	IS 3025 (Part 5)	Agreeable	Agreeable	Agreeable
6.	Iron (as Fe)	mg/l	IS 3025 (Part 2)	1.0	No relaxation	0.07
7.	Free residual chlorine	mg/l	IS 3025 (Part 26)	Min. 0.2	1	< 0.1
8.	Total dissolved solids	mg/l	IS 3025 (Part 16)	500	2000	154
9.	Fluoride (as F)	mg/l	IS 3025 (Part 60)	1.0	1.5	0.13
10.	Cyanide (as CN)	mg/l	IS 3025 (Part 27)	0.05	No relaxation	< 0.005
11.	Chloride (as Cl)	mg/l	IS 3025 (Part 32)	250	1000	27.43
12.	Total Alkalinity (as CaCO ₃)	mg/l	IS 3025 (Part 23)	200	600	31.59
13.	Total hardness (as CaCO ₃)	mg/l	IS 3025 (Part 21)	200	600	66.55
14.	Total Carbonate	mg/l	IS 3025 (Part 51)	--	--	Absent
15.	Bicarbonate	mg/l	IS 3025 (Part 51)	--	--	34.58
16.	Calcium (as Ca)	mg/l	IS 3025 (Part 40)	75	200	18.52
17.	Magnesium (as Mg)	mg/l	IS 3025 (Part 46)	30	100	4.93
18.	Sulphate (as SO ₄)	mg/l	IS 3025 (Part 24)	200	400	17.24
19.	Nitrate (as NO ₃)	mg/l	APHA Method	45	No relaxation	< 2
20.	Sodium (as Na)	mg/l	IS 3025 (Part 45)	--	--	3.16
21.	Potassium (as K)	mg/l	IS 3025 (Part 45)	--	--	1.07

NOTES: ● Please see watermark "Original Test Report" to confirm the authenticity of this report. ● Results shall be referred to tested sample(s) and applicable to tested parameters only. ● Test report shall not be reproduced except in full without prior written approval of Anacon Labs. ● Liability of Anacon Labs is limited to invoiced amount only. ● Non-perishable and perishable sample(s) shall be disposed off after 30 days and 15 days respectively from the date of issue of Test Report, unless specified otherwise. ● #Permissible limit in absence of an alternate source for drinking water. ● MPN indicates most probable number. ● 'mg/l' is equivalent to 'ppm'. ● 'µg/l' is equivalent to 'ppb'. ● '<' indicates detection limit of instrument/method and shall be considered as 'absent'. ● Result for test no. 7 is not relevant.

FOR ANACON LABORATORIES PVT. LTD.

Verified by

Head Office: Roshan Prakar, Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
 Lab : P.P. S.S. Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
 Support Head Office: Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
 Email : support@anacoin.in. You may also visit us at www.anacoinlaboratories.com

Authorized Signatory

(Mrs.) S.D. Garway
(Director - Labs)

Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Test Report No. : ALPL/26022019/664

Page 2 of 2

Issued To : Infosys Limited Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.	Sample Inward No. 1819/Mon-422-DW-1	Analysis Start 22.02.2019
	Inward Date 22.02.2019	Analysis End 26.02.2019
	P.O.NO. 2300129089	Report Issue Date 26.02.2019
	Date 04.06.2018	Sample Category Water
Sample Name Drinking Water	Sample Collected By Anacon Representative	Quantity Received 2 Lit. & 250ml
Sampling Location Canteen	Sampling Date 21.02.2019	Sampling Time 12.40 P.M.

TEST RESULTS

Sr. No	Test Parameter	Measurement Unit	Test Method	As per IS 10500 : 2012 (Drinking Water - Specification)		Test Result
				Acceptable Limit	*Permissible Limit	
22.	Dissolved Oxygen	mg/l	IS : 3025 (Part 38)	--	--	6.2
23.	Copper (as Cu)	mg/l	IS 3025 (Part 2)	0.05	1.5	< 0.03
24.	Manganese (as Mn)	mg/l	IS 3025 (Part 2)	0.1	0.3	< 0.05
25.	Mercury (as Hg)	mg/l	IS : 3025 (Part 48)	0.001	No relaxation	ND
26.	Cadmium (as Cd)	mg/l	IS : 3025 (Part 41)	0.003	No relaxation	< 0.001
27.	Selenium (as Se)	mg/l	IS : 3025 (Part 56)	0.01	No relaxation	< 0.001
28.	Arsenic (as As)	mg/l	IS : 3025 (Part 37)	0.01	No relaxation	< 0.01
29.	Aluminium (as Al)	mg/l	IS : 15302	0.03	0.2	< 0.005
30.	Lead (as Pb)	mg/l	IS : 3025 (Part 47)	0.01	No relaxation	< 0.001
31.	Zinc (as Zn)	mg/l	IS 3025 (Part 2)	5	15	< 0.01
32.	Total Chromium (as Cr)	mg/l	IS 3025 (Part 2)	0.05	No relaxation	< 0.03
33.	Boron (as B)	mg/l	IS 3025 (Part 2)	0.5	2.4	< 0.1
34.	Phenolic compounds (as C ₆ H ₅ OH)	mg/l	IS 3025 (Part 43) :1001	0.001	0.002	< 0.001
35.	Anionic detergents (as MBAS)	mg/l	IS 13428:2005 (Annex K)	0.2	1.0	< 0.01
36.	Total coliform	Per 100 rhl	IS 15185	Absent	Absent	Absent
37.	<i>Escherichia coli</i>	Per 100 ml	IS 15185	Absent	Absent	Absent

NOTES: ● Please see watermark "Original Test Report" to confirm the authenticity of this report. ● Results shall be referred to tested sample(s) and applicable to tested parameters only. ● Test report shall not be reproduced except in full without prior written approval of Anacon Labs. ● Liability of Anacon Labs is limited to invoiced amount only. ● Non-perishable and perishable sample(s) shall be disposed off after 30 days and 15 days respectively from the date of issue of Test Report, unless specified otherwise. ● #Permissible limit in absence of an alternate source for drinking water. ● MPN indicates most probable number. ● 'mg/l' is equivalent to 'ppm'. ● 'µg/l' is equivalent to 'ppb'. ● '<' indicates detection limit of instrument/method and shall be considered as 'absent'. ● Result for test no. 7 is not relevant.

REMARKS: Based upon request of the party, sample was tested for above mentioned parameters only. Sample complies with IS:10500:2012, for test conducted, indicating that it is fit for drinking purpose with respect to tested parameters.

For ANACON LABORATORIES PVT. LTD.

Verified by

Authorized Signatory

Head Office: Infosys Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
 Lab : F.P. 31, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
 Support Hub: Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
 Email : support@anacoin.in. You may also visit us at www.anacoinlaboratories.com

Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

NOISE MONITORING REPORT

Report No.:-	AN/NE/IL/2018-19/663	Report Date:-	26/02/2019
Issued to :-	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Noise Monitoring (February-2019)	Sample Ref.No.	1819/Mon-N-422
Sample Drawn By	Anacon Representative	Data Received :	23.02.2019

SL. NO.	LOCATION	Date of Sampling	RESULT (dBA)	
			Day Time	Night Time
1.	Near Main Gate	20.02.2019	61.7	54.9
2.	Near DG Set	20.02.2019	58.2	46.1
3.	Near Canteen	20.02.2019	52.8	41.6
CPCB Standards				
Industrial Area			75	70
Residential Area			55	45

Thanks for utilizing our services.

Chemist:- *Sony*

Gang
Authorized Signatory



Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924; Email : ngp@anacon.in
Lab : FP-34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475; Email : labngp@anacon.in
Support Helpline : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Annexure - VII

Test Report

March 2019



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/719-1

Issue Date : 30/03/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-441-1
Sample Description : Ambient Air
Sample Drawn On : 25/03/2019 To 26/03/2019
Sample Drawn By : Anacon Representative
Sample Received On : 27/03/2019
Sampling Location : Near Main Gate
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 27/03/2019 To 28/03/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 28°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear


S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	61.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	24.9	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	11.3	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	28.1	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.403	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	7.3	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	9.6	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 80, Rajprabha Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
 EP 54 35, Poojara Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
 Support, Logistics, Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
 Email : support@anacon.in/ You may also visit us at www.anaconlaboratories.com
 Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

[Signature]
Authorized Signatory





TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/719-2

Issue Date : 30/03/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7,Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-441-2
Sample Description : Ambient Air
Sample Drawn On : 25/03/2019 To 26/03/2019
Sample Drawn By : Anacon Representative
Sample Received On : 27/03/2019
Sampling Location : **Near DG Set**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 27/03/2019 To 28/03/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 28°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	56.1	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	21.7	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	8.1	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	23.9	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.352	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	6.8	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	8.1	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Saijyothi Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
 Branch Office : 35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
 Support Helpline : Chhatisgarh (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
 Email : support@anacoin.in / You may also visit us at www.anacoinlaboratories.com
 Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

[Signature]
Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2018-19/719-3

Issue Date : 30/03/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1819/Mon-441-3
Sample Description : Ambient Air
Sample Drawn On : 25/03/2019 To 26/03/2019
Sample Drawn By : Anacon Representative
Sample Received On : 27/03/2019
Sampling Location : Near Canteen
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 27/03/2019 To 28/03/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 28°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.4 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	51.3	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	CPCB Guidelines Volume1	18.4	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	6.7	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	16.9	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.313	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	CPCB Guidelines Volume1	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	CPCB Guidelines Volume1	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	CPCB Guidelines Volume1	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	CPCB Guidelines Volume1	5.6	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	CPCB Guidelines Volume1	8.2	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : P-5, Bopra Bhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacoin.in
 Branch Office : P-5, Bopra Bhu Nagar, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacoin.in
 Support Helpline : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
 Email : support@anacoin.in. You may also visit us at www.anacoinlaboratories.com
 Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

NOISE MONITORING REPORT

Report No.:-	AN/NE/IL/2018-19/719	Report Date:-	30/03/2019
Issued to :-	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7,Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Noise Monitoring (March-2019)	Sample Ref.No.	1819/Mon-N-441
Sample Drawn By	Anacon Representative	Data Received :	27.03.2019

SL. NO.	LOCATION	Date of Sampling	RESULT (dBA)	
			Day Time	Night Time
1.	Near Main Gate	25.03.2019	58.7	43.9
2.	Near DG Set	25.03.2019	52.1	41.6
3.	Near Canteen	25.03.2019	47.3	38.2
CPCB Standards				
Industrial Area			75	70
Residential Area			55	45

Thanks for utilizing our services.

Chemist:- *smf*

Gang
Authorized Signatory



Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924. Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helplines : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2008, ISO 14001:2004, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

STACK EMISSION REPORT

Report No.:-	AN/SE/IL/2018-19/720	Report Date:-	30/03/2019
Issued to	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7, Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Stack Monitoring (March-2019)	Sample Ref.No. :-	1819/Mon-441-S1
Sample Drawn By :	Anacon Representative	Sample Received Date	27.03.2019
Date of Analysis	27.03.2019 To 28.03.2019	Testing Period	01 day

Sr. No.	Parameters	Units	DG Set (160 kVA)
1.	Date of Sampling	-	25.03.2019
2.	Flue gas Temperature	°C	143
3.	Flue Gas Velocity	m/ sec	14.52
4.	Particulate Matter (PM)	mg /Nm ³	41.7
5.	Oxide of Nitrogen (NO _x)	mg /Nm ³	219
6.	HC	mg /Nm ³	112
7.	CO	ppm	327

Thanks for utilizing our services.

Chemist: *Smyf*

Gang
Authorized Signatory



Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helplines : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078, 9975947666) Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

Annexure - VII

Test Report

May 2019



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2019-20/85-1

Issue Date : 27/05/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1920/Mon-61-1
Sample Description : Ambient Air
Sample Drawn On : 21/05/2019 To 22/05/2019
Sample Drawn By : Anacon Representative
Sample Received On : 23/05/2019
Sampling Location : **Near Main Gate**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 23/05/2019 To 24/05/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 39°C
Average Flow Rate of SPM : 1.1 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	64.9	µg / m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	USEPA-40 (Part 50)	26.1	µg / m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	11.8	µg / m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	23.6	µg / m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.371	mg / m ³	2.0 (8 hrs)
6	Lead (as Pb)	IS:5182 (Part 22)	< 0.01	µg / m ³	1.0 (24 hrs)
7	Nickel (as Ni)	SOP ANqd/Mon-4	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	SOP ANqd/Mon-3	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	IS:5182 (Part 9)	6.1	µg / m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	Indophenol Method	9.3	µg / m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg / m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Chemist: *S. M. P.*

S. Jayaramkar
Authorized Signatory

Head Office : 40, Rajajinagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacnlabs.com
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacnlabs.com
Support Helplines : Technical (9373287475), Accounts Division (9328960081, 9372960079), Administration (9372960078)
Email : support@anacnlabs.com. You may also visit us at www.anacnlabs.com

Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2019-20/85-2

Issue Date : 27/05/2019

Issued To : **Infosys Limited**
Nagpur SEZ Co-Developer,
Plot No.7,Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1920/Mon-61-2
Sample Description : Ambient Air
Sample Drawn On : 21/05/2019 To 22/05/2019
Sample Drawn By : Anacon Representative
Sample Received On : 23/05/2019
Sampling Location : **Near DG Set**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 23/05/2019 To 24/05/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 39°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	53.9	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	USEPA-40 (Part 50)	21.8	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	8.1	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	18.6	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.352	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	IS:5182 (Part 22)	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	SOP ANqd/Mon-4	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	SOP ANqd/Mon-3	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	IS:5182 (Part 9)	5.6	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	Indophenol Method	8.1	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Chemist: *Smil*

Prayankar
Authorized Signatory

Head Office : 60, Durgam Chouk, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924. Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helplines : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

Ambient Air Quality Analysis Report

Report Code : AN/AA/IL/2019-20/85-3

Issue Date : 27/05/2019

Issued To : Infosys Limited
Nagpur SEZ Co-Developer,
Plot No.7, Sector-17, Special Economic Zone,
Mihan Notified Area,
Nagpur-441 108.

Inward No. : 1920/Mon-61-3
Sample Description : Ambient Air
Sample Drawn On : 21/05/2019 To 22/05/2019
Sample Drawn By : Anacon Representative
Sample Received On : 23/05/2019
Sampling Location : **Near Canteen**
Sampling Plan & Procedure : SOP-AAQ
Analysis Duration : 23/05/2019 To 24/05/2019
Sampling Time : 24 Hrs.
Ambient Temperature : 39°C
Average Flow Rate of SPM : 1.2 (m³/min)
Average Flow Rate of Gases : 0.3 (lpm)
Weather Conditions : Clear

S. No.	PARAMETER	TEST METHOD	RESULTS	UNIT	CPCB Standard
1	Particulate Matter (PM ₁₀)	IS:5182 (Part 23)	51.7	µg /m ³	100 (24 hrs)
2	Particulate Matter (PM _{2.5})	USEPA-40 (Part 50)	19.3	µg /m ³	60 (24 hrs)
3	Sulphur dioxide (as SO ₂)	IS:5182 (Part 2)	7.6	µg /m ³	80 (24 hrs)
4	Nitrogen dioxide (as NO _x)	IS:5182 (Part 6)	18.4	µg /m ³	80 (24 hrs)
5	Carbon Monoxide (as CO)	IS:5182 (Part 10)	0.349	mg /m ³	2.0 (8 hrs)
6	Lead (as Pb)	IS:5182 (Part 22)	< 0.01	µg /m ³	1.0 (24 hrs)
7	Nickel (as Ni)	SOP ANqd/Mon-4	< 0.1	ng / m ³	20.0 (annual)
8	Arsenic (as As)	SOP ANqd/Mon-3	< 0.1	ng / m ³	6.0 (annual)
9	Ozone (as O ₃)	IS:5182 (Part 9)	5.7	µg /m ³	100 (8 hrs)
10	Ammonia (as NH ₃)	Indophenol Method	8.6	µg /m ³	400 (24 hrs)
11	Benzene (as C ₆ H ₆)	IS:5182 Part 11-GC	< 0.01	µg /m ³	5.0 (annual)
12	Benzo-Pyrene (as BaP)	IS:5182 Part 12-GC	< 0.01	ng / m ³	1.0 (annual)

Thanks for utilizing our services.

'<' Indicates Absent.

Head Office : 60, Chhatrasagar Nager, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924. Email : ngs@anacon.in
 Chemist : S. P. J. For Office : Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373267475. Email : labngp@anacon.in
 Support Helpline : Technical (9373267475), Accounts Division (9326960081, 9372960079), Administration (9372960079)
 Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com

Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi

S. P. J.
Authorized Signatory



TEST REPORT

ANACON LABORATORIES PVT. LTD.

ISO 9001:2015, ISO 14001:2015, OHSAS 18001 Certified Organization,
Recognized By Ministry of Environment & Forests (MoEF), New Delhi
Accredited By Quality Council of India by NABET - Environment Impact Assessment Studies
Authorised by Food Safety & Standards Authority of India Under FSS Act
Approved by Bureau of Indian Standards (BIS)

NOISE MONITORING REPORT

Report No.:-	AN/NE/IL/2019-20/85	Report Date:-	27/05/2019
Issued to :-	Infosys Limited	Address :-	Nagpur SEZ Co-Developer, Plot No.7, Sector-17, Special Economic Zone, Mihan Notified Area, Nagpur-441 108.
Type of Work :-	Noise Monitoring (May-2019)	Sample Ref.No.	1920/Mon-N-61
Sample Drawn By	Anacon Representative	Data Received :	23.05.2019

SL. NO.	LOCATION	Date of Sampling	RESULT (dBA)	
			Day Time	Night Time
1.	Near Main Gate	21.05.2019	62.8	56.1
2.	Near DG Set	21.05.2019	57.3	43.9
3.	Near Canteen	21.05.2019	53.7	38.2
CPCB Standards				
Industrial Area			75	70
Residential Area			55	45

Thanks for utilizing our services.

Chemist:- *Smyf.*

Praygankar
Authorized Signatory



Head Office : 60, Bajiprabhu Nagar, Nagpur - 440033 India. Ph. No. (0712) 2242077, 9372404924, Email : ngp@anacon.in
Lab : FP 34-35, Food Park, Five Star Estate, MIDC Butibori, Nagpur - 441122. Mob. No. 9373287475, Email : labngp@anacon.in
Support Helplines : Technical (9373287475), Accounts Division (9326960081, 9372960079), Administration (9372960078)
Email : support@anacon.in. You may also visit us at www.anaconlaboratories.com
Branches : Maharashtra | Chhattisgarh | Madhya Pradesh | Jharkhand | Delhi